



TECHNICAL DESCRIPTION

Number of modules	10
Type of modules	ComfortLine
Dimensions of modules	9,000x3,600x5,045 mm 9,000x3,600x3,610 mm
Area	324 m ²
Internal height	4,340 mm, 2,905 mm
Length of manufacture	2 weeks
Length of assembly	4 weeks
Windows	Plastic frames, double glazing
External doors	Plastic frames, double glazing, laminated safety glass
Interior – walls	Gypsum fibreboard with painting, ceramic large-format tiles in bathrooms, sanitary partitions
Interior - floors	Laminated hardwood flooring, heavy-duty carpet, PVC, tiles
Facade	Plastered facade
Heating	Radiant ceiling panels, electric heaters
Fire resistance	15 min., mixed construction system DP2
Equipment	Porch, Internal door with architrave frames, cleaning zone, fire extinguishers

Description

The 324m² culture house is assembled from 10 ComfortLine large-format modules. The main hall, with a clearance 4.3m, consists of 6 modules and was supplied as a flatpack system. The auxiliary rooms, including a kitchen, a lavatory, storerooms, and a clubroom, and are made from 4 standard modules having a clearance of 2.9m.

The hall is heated with ceiling radiant panels and the auxiliary rooms are heated with electric heaters.

A Culture House

Site location	Rybník, Czech Republic
Implementation date	November 2013
The delivery included:	Supply of upper building.
The delivery didn't include:	Predecessor activities.

