Number: 102-302-p.1 Revision: 2020

KOMA Factory Restaurant





TECHNICAL DESCRIPTION

Number of modules	19
Type of modules	ComfortLine, Light
Dimensions of modules	2pcs 7,500x3,300x3,315 mm 7pcs 9,000x3,300x3,315 mm 1pcs 7,500x3,290x3,315 mm 9pcs 9,000x3,290x3,995 mm
Area	541 m2
Internal height	2,608 mm
Length of manufacture	3 weeks
Length of assembly	8 weeks
Windows	Aluminium, double glazing, charcoal grey, external electric roll-up screens
External doors	Aluminium, double glazing, charcoal grey
Interior – walls	Gypsum fibreboard with painting, Waterproof wallpaper in sanitary rooms
Interior - floors	Gypsum fibreboards, PVC
Facade	Facade from expanded mesh, Glass façade, PUR panel
Heating	Hot water heating
Fire resistance	30 min., non-flammable construction system DP1
Equipment	Secondary pen roof, Gastro equipment, Ventilation and A/C system, Solar system

Description

A new modular building designed by Chybik+Kristof Architectural Studio. Their design offers an elegant building interior solution in attractive colours reflecting the latest trends and creating a lush and pleasant impression.

Thanks to the large windows, the building is well-lit. The exterior solution makes an attractive impression. It is not only an interesting mix of modules and terrace, but also an imaginative facade solution.

The building's water heating is handled with solar collectors and lavatories are flushed using rainwater.


KOMA Factory Restaurant

Site location	Říčanská 1191, Vizovice, Czech Republic
Implementation date	November 2013
The delivery included:	Supply of upper and lower building incl. utility lines.
The delivery didn't include:	-

Number: 102-302-p.2 Revision: 2020

KOMA Factory Restaurant















Number: 102-302-p.3 Revision: 2020

KOMA Factory Restaurant



